BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2019-20/OW/WORK_INDENT38321/CALL-3

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/19/2019-20, Date: 30.11.2019

Asphalting to Roads in Tatanagar in ward no 08 Kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of A S MANI (S S ROAD DEVOLOPERS) In Figures		In Words
1	1978	Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries complete as per specifications. MORTH V revision	sqm	133.0	263074.00	Rupees One Hundred Thirty Three Only
2	296.7	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification No. 406	cum	2001.0	593696.70	Rupees Two Thousand One Only
3	1978	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification No. 500	Sqm	22.0	43516.00	Rupees Twenty Two Only
4	1978	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/Sqm over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries complete as per specifications.	Sqm	46.0	90988.00	Rupees Forty Six Only
5	21.75	KSRRB M500-18: Providing and laying bituminous macaduam on prepared surface using crushed aggregates as per design mix formula for base/binding course including loading of aggregates with FE loader, hot mixing of stone aggregates and bitumen in hotl mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. Using 40-60 TPH capacity HMP with mechanical paver grading II (50-75mm) with 3.4% VG-30 bitumen. (Page No. 159, Item No. 21.11.6, PWD SR 2018-19)	cum	6172.0	134241.00	Rupees Six Thousand One Hundred Seventy Two Only
6	79.12	Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 40-60 TPH capacity HMP with mechanical paver grading I (35-40mm) with 4.5% VG-30 Bitumen	cum	7717.0	610569.04	Rupees Seven Thousand Seven Hundred Seventeen Only
7	58	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.	Sqm	454.0	26332.00	Rupees Four Hundred Fifty Four Only

Signature of the contractor

18/12

Executive Engineer

18/12

Approved Qty.	Description	Unit	Approved Tender Rates of A S MANI (S S ROAD DEVOLOPERS)		
			In Figures		In Words
148.35	ead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading with all leads and lifts as directed by the Engineer in charge of the work.	cum	101.0	14983.35	Rupees One Hundred One Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92